

### Scope of works for the Cape town OC

- The service provider is required to supply, install and commission additional network Cameras to the existing cctv system. All accessories like network cables, etc. should be supplied by the service provider.
- The service provider must leave the system full operational.
- The existing system is built around AXIS network cameras. The required cameras should be the same or equivalent to the current cameras.
- Two additional monitoring feeds to be installed, one in the OC Managers office and one provision to be made for the future guard house
- The number of additional Cameras required is 14 (***a combination of dome and bullet cameras, similar/equivalent to Axis P1455-LE and P3265 LV***)
- It is important to note that equivalent and or similar cameras must be compatible to the current system of cameras. That is why the site briefing is very important.
- A minimum of a 48port 10/100Mbps fast ethernet switch is required.
- If there are any additional mains power point, the service provider will be responsible for such and will issue a COC for the additional power points. The Sentech electrician will monitor this part of the work.